KOLAR DIVISION.

Notification dated 28th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 17th April 1933, for the work of restoring Tyranahally Lakkikere, Reg. No. 709 of Bowringpet Taluk." An approximate estimate of quantities is give below. These quantities are not guaranteed. The work should be completed by the end of March 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and twenty only in cash or currency notes, as earnest money, and be superscribed " Tender for the work of restoring Tyranahally Lakkikere, Regd. No. 709 of Bowringpet Taluk," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual Contract Bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited,

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be entered both in words and figures else the tender will be rejected.

Abstract estimate for Restoring Tyranahalli Lakkikere of Bowringpet Taluk Regd. No. 709

Serial No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		
1	Earth work to bund including watering and tamping with lead and lift.	Cyd.	0 3 6	7,765	1,699
2	Turfing to bund ...	S.yds	0 1 0	4,062	254
3	Removing and resetting old revetment stone with new jelly as per statement.	Cyds.	0 10 0	719·44	450
4	New stone work as per statement ...	,,	1 10 0	469	762
a	Collecting Jelly for old revetment ...	,,	0 10 0	36	23
5	Preparing and fixing new grade stones with painting and chisteling.	Each	1 8 0	4	6
6	Chisteling and painting old grade stones ..	,,	0 12 0	13	10
7	Preparing and fixing index stones ..	,,	0 8 0	17	9
8	Do B. M. Stones. ...	,,	2 8 0	2	5
9	Do Reg. No. Date stones ...	,,	4 0 0	1	4
10	Do Gauge stone with painting.	No.	15 0 0	1	15
11	Cutting trenches and grips in old bund to join new earth.	Grade	2 0 0	16	32
12	Clearing prickly-piers and Jungle ...	,,	2 0 0	16	32
	Total Bund ..	...	...	...	3,365

Serial No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice No. 1 :—*R. L.* 45·00		Rs. a. p.		
1	Earth work cut opening the bund ..	Cyd.	0 3 6	38	8
2	Stone jelly concrete in surki mortar ...	C.ft.	0 4 6	113	32
3	Burnt brick in surki mortar ..	"	0 5 0	311	97
4	Burnt stone slabs 6" thick ..	S.ft.	0 5 0	112	35
5	Surki plastering ...	Sqr.	4 8 0	2	9
6	Providing cast iron pipe 5" dia including carting and jointing with cement complete.	R.ft.	2 0 0	36	72
7	Cutting holes in upper and lower orifice..	No.	1 0 0	3	3
	Providing plug and rod with locking arrangements.	Lump	sum	...	15
	Refilling with watering and tamping as per excavation.	Cyds.	0 3 6	39	8
	Total Sluice ...	..		...	279
	Sluice No. 2 :—				
	Same as per No. 1 sluice ...	...	...	...	279
	Waste Weir at R. L. 52·00—				
1	Approach draft clearing ...	Lump	sum	...	100
2	Excavating foundation ...	Cyd.	0 3 6	20	4
3	Concrete in surki ...	C.ft.	0 4 6	383	108
4	Burnt stone slabs ...	S.ft.	0 5 0	247	77
5	Plastering with surki mortar ...	Sqr.	4 8 0	4·37	8
6	Cutting Joggle joints ...	No.	0 12 0	11	8
	New stone work apron ...	Cyds.	1 10 0	39	63
	Total weir ...	...	...	...	449
	Total of Bund and Sluices and Weir—				
	= 3365 + 558 + 449 ...	....	...	..	4,372

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 9th March 1933.

Subject :—Constructing an Urdu Middle School Building at Kunigal.

The attention of the public is drawn to Notification calling for tenders for the above work in pages 319 and 320, Part VI of the *Mysore Gazette*, dated 23rd March 1933.

The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 18th April 1933.

An earnest money of Rs. 350 should accompany the tender.

Notification, dated 28th March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 26th April 1933, for opening a road from Gubbi to Chitnahalli (Chandrasekharapura) in Gubbi Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.